

PART IV: SCOPE OF WORK

KINGSBURY MIDDLE AND HIGH SCHOOL EXTERIOR FIELD LIGHTING

This location is a New Build. There is no Sport Lighting on site.

The contractor is to provide labor and materials for the new LED Sport Field Lighting at Kingsbury Middle and High School.

The soccer field is to maintain an average of 30 horizontal foot candles of light at the playing surface.

The contractor is responsible for the design and build of a 10x10 cinder block building with metal roof, interior and exterior lighting, and convenience outlets to serve as electrical room and field equipment storage.

Contractor to furnish and install new basic, wirelessly controlled scoreboard in place of existing scoreboard.

Fixtures to have a 25-year warranty, which shall cover Labor and Materials for the duration of the 25-year warranty.

Contractor to verify existing lighting voltage prior to ordering fixtures.

The contractor is to properly dispose of used HID lamps and remove all existing fixtures from premises.

Any substitution request must be submitted during the Questions period.

Please see the MSCS Design Planning Principles and Construction Guidelines as well drawings posted on the Procurement Services website under the IFB template.